

# Canyon Regional Water Authority

## Request for Bids

The Canyon Regional Water Authority (CRWA) will be accepting bids for the purchase of certain items required for the installation of a well pump, motor, and appurtenances. These items are more specifically listed below. (See Attached Map for Location)

Hereby Referenced as

### **Wells Ranch III (Phase I)**

#### Well Equipment:

- 1 each – Flowserve Cast Steel  
Pump End 10” 4 Stg  
1100 gpm @ 540 ft. 130 PSI \$ \_\_\_\_\_
- 1 each - SME Stainless Steel Motor 200 HP  
10” 460 V 3ph 2P. \$ \_\_\_\_\_
- 800 ft. - Jackted Cable w/Grd 200 MCM 3  
Conductor \$ \_\_\_\_\_
- 340 ft. - 8” x .322” x 20’ 304 SS T& C  
w/NiA1Bz Line Pipe Coupling. \$ \_\_\_\_\_
- 1 each – Flowmatic 80DI 7939 Ductile Iron 8” Check Valve  
Epoxy Body and Dome, Spring, , Rubber Disk. \$ \_\_\_\_\_
- 1 each - Installation of Concrete Pad
  - (3000 PSI)
  - Pad (6 ft x 14 ft x 1 ft w/#4 Rebar on 1 ft Center
  - Beams 1 ft x 1 ft w/6 each #6 Rebar on Perimeter.\$ \_\_\_\_\_

Electrical Installation: (Installation includes from power supply to pump to generator)

- 1 each – 400 amp Disconnect, Riser, Fuses and wire to Panel. \$ \_\_\_\_\_
- 1 each – 200 HP VFD. \$ \_\_\_\_\_
- 1 each – 200 HP Sine Wave Filter. \$ \_\_\_\_\_
- 1 each – 400 amp Automatic Transfer Switch. \$ \_\_\_\_\_
- Approximately 100 ft of wire and Conduit needed to connect to Generator. \$ \_\_\_\_\_

Complete Well Equipment Installation:

- Labor to Remove Existing Well Equipment and the Installation of New Specified Equipment. \$ \_\_\_\_\_

Total Cost for the Equipment and Installation of the Specified Equipment. \$ \_\_\_\_\_

If you have any questions, please contact David McMullen at 512-581-8544.

(There will be NO substitutions unless specifically requested by CRWA Representative.)

All Documents for Bond Coverage shall accompany Bids. Bond Coverage shall be for amount of Bid.

Bids will be opened and read aloud by the General Manager (CRWA) at 10:00 am on **(Thursday) May 23, 2024**, at the Canyon Regional Water Office. Located at 850 Lakeside Pass, New Braunfels, Texas 78130.

The Contractor shall have the project completed within sixty (60) days after having received a certified letter to proceed.

---

**Contractor/Company**

---

**Date**